

NAME OF WORK : Providing parking facilities in existng ground of college of dairy science, Shedubhar, Amreli.

Schedule-B (Price Bid)

ITEM NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	P/F Steel work welded, in built up sections, framed work including cutting, hoisting, fixing in positioned applying a priming coat with red lead paint and applying two coats of enamel paint of approved shades etc. complete.	1890.00	Kg	60.00	113400.00
2	Providing & fixing 2.00 mm thick F.R.P. sheet of good quality and standard make rate also includes necessary fabrication structure in the grid of 1'-6" x 1'-6" size usiung hollow pipe of size 3/4" x 3/4" , 2" x 1" & 1" x 1" rate also inclusive necessary bending ,cutting and fabrication charges and priming coat and 2 coats of oil paint of shade approved by engineer in-charge rate also includes washer and silicon paste required for fixing the sheet in good quality as diredted.	50.00	Sqm	1865.00	93250.00
3	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead. (A) Loose or soft soil	150.00	Cum	67.23	10084.50
4	Filling available excavated earth (excluding rock) in trenches, plinth sides of foundation etc. in layers not exceeding 20 cms. in depth consolidating each deposited layer by ramming and watering.	100.00	Cum	76.47	7647.00
5	Providing and laying cement concrete 1:3:6 (1-Cement : 3- coarse sand : 6- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	20.00	Cum	2254.56	45091.20

6	Providing and laying controlled cement concrete M-200 and curing complete excluding the cost of formwork and reinforcement (A)Foundations, footings, base of columns and mass concrete.(A) Foundation, footing, base of column & mass concrete	60.00	Cum	3535.84	212150.4
7	P/A Trimix with dewatering machine and floater machine on constructed RCC work incl.cost of machine and labour etc comp as directed.	75.00	Sqm	54.00	4050.00
8	Providing Mild Steel Reinforcement of approved brand only for all R.C.C. work including cutting, bending, binding and placing in position etc. complete for all floors.	200.00	Kg	39.58	7916
9	Making 15 mm groove in RCC work on road and filling it with polysulfied selant and finished it good incl.all labour charges etc comp as directed.	30.00	RMT	30.00	900
					494489.10
	ADD LABOUR CESS	1.00%			4944.891
		TOTAL AMOUNT			499433.99

In Words: Four Lakh Ninety Nine Thousand Four Hundred Thirty Three and Ninety Nine Paise only

I/We am/are willing to carry out the work at% above/below percent (should be written in figures and words) of the estimated rates mentioned above. Amount of my/our tender works out as under.

Estimated amount

Estimated amount

Put to tender Rs.499433.99

Put to tender Rs 499433.99

Deduct% below Rs.....

Add% above Rs.....

Net Rs.....

Total Rs.....

In words

In words

(*Please strike out whichever is not applicable).

(છેકછાક કરેલ અથવા વાઈટનર થયેલ પ્રાઈઝ બીડ અમાન્ય રહેશે.)

Signature of Contractor.

Executive Engineer
Kamdhenu University