

# Construction of Parking Shed at Rajpura (Nava) Himmatnagar

## ABSTRACT

Item No.	Item Description	Quantity	Unit	Rate	Amount
1	<b>Excavation</b> for foundation Up To 1.5 m Depth including sorting out and stacking of useful materials and disposing of the excavated stuff for all lead and lift including refilling of trenches for Loose or soft soil... etc., complete as directed by E.I.C.				
		70.37	cum	67.23	4730.84
2	<b>Supplying &amp; spreading of graded stone 40 mm to 63 mm size aggregate of shed inside</b> etc complete as directed by EIC....				
		30.00	cum	359.82	10794.60
3	<b>Supplying &amp; spreading of Murrum/binding</b> material for shed with compaction as directed by EIC.				
		18.00	cum	156.71	2820.78
4	Providing & laying Cement Concrete 1:2:4 (1 cement : 2 coarse :4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in <b>GROUND FLOOR PLINTH SLAB</b> complete as directed by E.I.C.				
		21.00	cum	3359.54	70550.34
5	Providing & Laying twisted <b>TMT Bar reinforcement</b> (as per is code Fe-415) of TATA-Tisco, Nilkanth, Kamdhenu, NRE, National or Friends make for RCC work including cleaning, bending, binding and placing in position with 16 gauge annealed wires... etc. completed as per detailed structural drg & details directed by E.I.C. for ground floor				
		1260.00	kg	44.25	55755.00
6	Providing and erecting of <b>Steel work welded</b> in built up sections frames work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint with painting two coats of enamel (A) in beams and joints, channels angles, Tees, flats with connecting plates or angle cleats as in main and cross beams. Hip and jack rafters, purlins connected to common rafters and the like roof etc complete. as directed by EIC				
		4500.00	kg	60.13	270585.00

7	Providing , laying and fixing Color Coated Galvlume Sheet 30 mm crest depth in length as per site requirement. The fed material is to be manufactured out of 0.50mm (TCT) thick, 550 Mpa Steel with zinc-aluminum alloy of AZ-150GSM. The sheet shall have a hot dip metallic zinc-aluminum alloy coating of zinc (45%) & aluminum (55%) with total mass coating of 150gsm/sqm on both sides.& 1.6% Silicon coating, The profile is having return leg for proper side lap. Complete as per specifications.Fixing of sheet with galvanized iron J or L hook,bolts and nuts 8mm dia. with bitumen and G.I. limpet washer, filled with white lead.				
		165.00	sqm	454.50	74992.50
					490229.06
	ADD LABOUR CESS 1 %	1.00	%		4902.29
				<b>TOTAL</b>	<b>495131.35</b>

I / We am / are willing to carry out the work at ..... % above / bellow percent (should be written in figure and words) of the estimated rate mentioned above. Amount of My / Our tender works put as under.

Estimated Amount

Put to tender Rs 495131.35

Deduct .....% Below Rs .....

Net Rs.....

In Words .....

Estimated Amount 495131.35

Put to tender Rs Put to tender Rs.....

Add .....% Above Rs .....

Total Rs.....

In Words .....

Signature of Contractor

Executive Engineer  
Kamdhenu University